

Soda Gun Jetter Machine Pre-Installation Checklist

The purpose of our pre-installation checklist is to provide you with some guidance regarding what is required to successfully install a commercial Soda Gun Jetter. It is not an exhaustive list.

For most of our customers, they skim the pre-installation checklist below. If they can answer “yes” to the items on list, the installation should go smoothly and we can get a Soda Gun Jetter installed quickly.

Here’s a way that might help you remember. Most people have heard about the “Honey- Do” list. We call our pre-installation checklist the “**Honey-DEWS**” list:



- D** – Drain
- E** – Electricity
- W** – Water
- S** – Space

Drain:

- Floor Drain
- Within 6 feet of each soda gun
- Allows for ¼ inch fall for every foot of drain pipe
- Doesn't present a tripping hazard

Electricity:

- 110V GFCI protected outlet within 6' of the Soda Gun Jetter Control box location.

Water:

- Filtered water line capable of delivering 5 gallons per minute in close proximity of the Soda Gun Jetter Control box location.

Space:

- Allow enough space for mounting of the Soda Gun Jetter Control box.